

N

NOTES

THIS SURVEY IS ORIENTATED TO ORDNANCE SURVEY GRID NORTH. THE SURVEY IS TO A PLANE GRID. HORIZONTAL MEASUREMENTS TAKEN FROM THIS SURVEY WILL BE GROUND DISTANCES.

SITE CENTRE: E 348879, N 359320

LOCAL SCALE FACTOR: 0.9996334

ALL LEVELS RELATE TO ORDNANCE SURVEY DATUM GENERATED BY ACTIVE GPS NETWORK.

DRAINAGE:-

NO ALLOWANCE HAS BEEN MADE FOR SUB SURFACE ACCESS TO MANHOLES OR INSPECTION BOX TYPE BELOW GROUND DIRECTLY FROM THE SURFACE OR FROM THE SURFACE AND TRUS WILL ONLY BE APPROXIMATE. ANY FLOW TYPES (FOUL WATER, SURFACE WATER OR COMBINED) ARE ASSUMED AND THEREFORE REQUIRE VERIFICATION.

ROAD MARKINGS:-

ROAD MARKINGS DISPLAYED ARE SYMBOLIC. LENGTH, SPACING AND THICKNESS ETC ARE INDICATIVE ONLY.

LEGEND

- 362.9 SPOT LEVEL
- SURVEY STATION
- SAPLING
- BUSHES/SHRUB
- TREE (INDICATIVE ONLY)
- HEDGE/AREA OF UNDERGROWTH
- 99.00 CONTOUR
- GATE
- OVERHEAD CABLE
- FENCE
- 1 PHOTOGRAPH LOCATION AND NUMBER

ABBREVIATIONS

AA	ARCH LEVEL	LB	LETTER BOX
AV	AIR VALVE	LP	LAMPOST
BB	BUS BOX	MH	MANHOLE
BC	BOLLARD BEACON	MK	MARKER
BH	BOREHOLE	OHC	OVERHEAD CABLE
BL	BICI LEVEL	OL	OPENING LEVEL
BS	BUS STOP	OSBM	OS BENCHMARK
CB	CATCH PIT	P	POST
CB	CLOSED BOARD FENCE	PR	POST AND RAIL FENCE
CA	CHAIN LINK FENCE	PW	POST AND WIRE FENCE
CaTV	CABLE TELEVISION COVER	PEC	PEDESTRIAN CROSSING
CC	CONTROL CABIN	PM	PARKING METER
CL	CROWN LEVEL	PL	PARKING LEVEL
Conc/p	CONCRETE PANEL FENCE	RWL	RETAINING WALL
CPY	CANOPY	SAP	SAPLING
CL	CROWN LEVEL	SEC	SECURITY CAMERA
Cstv	CABLE STAY	SGY	STRIP GULLY
CTP	CABLE TV DIVISION POINT	SL	SPRINGING LEVEL
CYK	CYCLE RACK	SP	SIGNPOST
DK	DROPPED KERB	Spl.	SPRINGING LEVEL
DP	DOWNPIPE	SV	STOP VALVE
EP	ELECTRIC INLET POINT	Tac	TACTILE PAVING
EP	ELECTRICITY DISTRIBUTION COVER	TBS	TRAFFIC BOLLARD
EP	ELECTRICITY SUPPLY POLE	TE/7	TREE = NUMBER
ER	EARTH ROD	THL	THRESHOLD LEVEL
FH	FIRE HYDRANT	TL	TOP OF LEDGE
FL	FIELD LEVEL	ToF	TOP OF FENCE
G/DP	GULLY AND DOWNPIPE	ToW	TOP OF WALL
GP	GATE POST	TP	TELEPHONE POLE
GP	GAS PIPE	WM	WIRE MESH FENCE
GV	GAS VALVE	WF	WOODEN RAIL FENCE
IC	INSPECTION CHAMBER	WLV	WATER LEVEL
IL	INVERT LEVEL	WM	WATER METER
IR	IRON RAILING FENCE	WO	WASH OUT
KO	KERB OUTLET		

STATION CO-ORDINATES

STATION	EASTING	NORTHING	LEVEL	DESCRIPTION
STN1	349040.68	359204.48	29.29	Survey Nail
STN2	349041.62	359293.30	29.48	Survey Nail
STN3	349040.47	359351.87	32.57	Survey Nail
STN4	349029.43	359126.18	31.97	Survey Nail

TREE SCHEDULE

No.	DIAM.	SPREAD Ø	HEIGHT
TE/1	1.20	24	20
TE/2	0.50	10	10
TE/3	1.30	19	16
TE/4	0.90	18	16
TE/5	0.90	18	16
TE/6	1.10	20	16
TE/7	1.10	22	16
TE/8	1.00	18	16
TE/9	0.90	16	16
TE/10	0.80	16	16
TE/11	1.00	16	18
TE/12	1.10	16	14
TE/13	0.95	20	18
TE/14	0.90	20	20
TE/15	0.75	20	20
TE/16	0.65	18	20
TE/17	0.80	18	18
TE/18	1.00	20	18
TE/19	0.50	10	8
TE/20	0.80	16	14
TE/21	0.80	12	14
TE/22	0.30	12	12

TREE DIAMETER MEASURED APPROXIMATELY 1.5M ABOVE GROUND LEVEL. TREE SPREADS ARE SYMBOLIC ONLY AND ARE REPRESENTATIVE OF THE GENERALISED CANOPY SIZE. TREE BOLE MAY NOT SIT CENTRALLY TO THE CANOPY. TREE HEIGHT ESTIMATED FROM GROUND LEVEL.

Rev	Date	Revision notes	By
*	*	*	*

DO NOT SCALE FROM THIS DRAWING

Status: **INFORMATION**

THE SURVEY ASSOCIATION AFFILIATE MEMBER

Project: **Tattenhall Road, Tattenhall.**

Title: **TOPOGRAPHICAL SURVEY AS OF 27.08.24 SHEET 1 OF 1**

GLADMAN
Gladman House, Alexandria Way
Congleton Business Park
Congleton, Cheshire
CW12 1LB
Tel: 01260 288800
Fax: 01260 288801
www.gladman.co.uk

Drawn By	Publish Date	Scale(s)	Sheet Size
JH	24.10.24	1:500	A0

Project no.	Drawing no.	Revision
2023-030	Topo_01_2D	0